BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
I I B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work: -Providing asphalting to old Post office road in ward No:01 of Yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP.	
				Rate	Rate in Words
1	KSRRB 300- Sacarifying the surface and dressing KSRRB 300-44: Scarifying top bituminous surface or surface dressing or premix carpet including picking up scarified materials, stacking of id serviceable materials within a lead of 100 meters by manual means including cost of all labour charges complete as per specifications MORTH chapter 3.	Sqm	900.00	17.93	Rupees seventeen and paise ninety three only
2	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of lipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification	Cum	285.00	1059.48	Rupees one thousand fifty nine and paise forty eight only
3	KSRRB 500-2: Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	1750.00	2.38	Rupees two and paise thirty eight only
4	KSRRB M500-6: providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH specification	Sqm	2650.00	42.83	Rupees forty two and paise eighty three only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
5	KSRRB 500-11: Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50 / 75mm compacted thickness with 3.3% bitumen but excluding cost of primer / tack cost with lead upto 1km including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5 With 60 / 70 grade bitumen.	Cum	60.20	6455.69	Rupees six thousand four hundred fifty five and paise sixty nine only
6	KSRRB 500-7: providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	2650.00	17.12	Rupees seventeen and paise twelve only
7	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing and average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications	Cum	66.25	9241.60	Rupees nine thousand two hundred forty one and paise eighty only
8	KSRRB M800-11.2: Painting lines, dashes, arrows etc. on roads in two coats on new work with ready mixed road marking paint conforming to IS: 164 on bituminous surface, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at site and traffic control complete as per specification ii) Upto 10cm in width MORTH specification	Sqm	159.00	87.48	Rupees eighty seven and paise forty eight only

Technical Manager-2
KRIDL, BBMP
Bangalore - 560 001
Signature of the Contractor

Executive Engineer
Shankara Division,
BBMP, Bengaluru-04

4/3/13